SEE STORMWATER MANAGEMENT REPORT FOR DESIGN DETAILS

INVERT SCHEDULE

WATER MAINS - ALL WATER MAINS TO BE AT DEPTH OF MINIMUM 5' TO TOP OF DUCTILE IRON WATER MAIN.

SANITARY SEWER - 8" SDR 35 PIPE

M.H. #1 RIM ELEV. = 342.3'±
INV. OUT TO MH#2 = 335.5'

M.H. #2 RIM ELEV. = 327.4'±
INV. IN FROM M.H. #1 = 320.6'
INV. IN FROM M.H. #9 = 316.5'
INV. OUT TO MH#3 = 316.25'

M.H. #3 RIM ELEV. = 321.5'±
INV. IN FROM M.H. #2 = 309.5'
INV. IN FROM M.H. #12 = 309.5'
INV. OUT TO M.H. #4 = 309.25'

M.H. #4 RIM ELEV. = 317.8'±
INV. IN FROM M.H. #3 = 306.9'
INV. IN FROM M.H. #5 = 306.0'
INV. OUT TO PUMP STATION = 305.75'

M.H. #5 RIM ELEV. = 316'±
INV. IN FROM M.H. #6 = 308.25'
INV. IN FROM M.H. #10 = 308.25'
INV. OUT TO M.H. #4 = 308.0'

M.H. #6 RIM ELEV. = 320'±
INV. IN FROM M.H. #7 = 311.75'
INV. OUT TO M.H. # 5 = 311.50'

M.H. #7 RIM ELEV. = 322.2'±
INV. IN FROM M.H. #8 = 313.2'
INV. OUT TO M.H. #6 = 313.0'

M.H. #8 RIM ELEV. = 323.5'±
INV. OUT TO M.H. #7 = 317.5'

MH8A RIM ELEV= 324.5'±
INV OUT TO MH8 = 319.6'

M.H. #9 RIM ELEV. = 324.9'±
INV. OUT TO M.H. #2 = 319.25'

M.H. #10 RIM ELEV. = 318.3'±
INV. OUT TO M.H. #5 = 310.5'

MH#10A RIM ELEV= 319.5'±
INV OUT TO MH10 = 313.5'

M.H. #11 RIM ELEV. = 318.5'±
INV. OUT TO M.H. #12 = 313.52'

MH#12 RIM ELEV= 318'±
INV IN FROM MH#11 = 311.8'
INV OUT TO MH3 = 311.5'

STORM SEWER - 12"-24" DIA. HDPE PIPE

C.B.1 RIM ELEV. = 326.85'±
INV. OUT TO C.B.2 = 322.25'
INV IN FROM CB1A = 322.5'

CB1A RIM ELEV= 326.85'±
INV OUT TO CB1 = 323.02'

C.B.2 RIM ELEV. = 326.25'±
INV. IN FROM C.B.1 = 321.5'
INV. OUT TO C.B.3 = 320.85'

C.B.3 RIM ELEV. = 321.75'±
INV. IN FROM C.B. 2 = 316.5'
INV. OUT TO C.B.4 = 316.25

C.B.4 RIM ELEV. = 320.25'±
INV. IN FROM C.B.3 = 315.0'
INV. OUT TO C.B.6 = 312.5'

C.B.5 RIM ELEV. = 317.25'±
INV. OUT TO C.B.6 = 309.8'

C.B.6 RIM ELEV. = 317.25'±
INV. IN FROM C.B.5 = 309.28'
INV. IN FROM C.B.4 = 309.15'
INV. IN FROM C.B.7 = 307.15'
INV. OUT TO DETENTION BASIN = 306.9'

C.B.7 RIM ELEV. = 316.7'±
INV. IN FROM C.B.8 = 310.5'±
INV. IN FROM C.B.9 = 309.8'
INV. OUT TO C.B.6 = 309.55'

C.B.8 RIM ELEV. = 318.24'±
INV. IN FROM C.B. 8A = 313.98'
INV. OUT TO C.B 7 = 313.73'

C.B.8A RIM ELEV. = 318 24'±
INV. OUT TO C.B. 8 = 313.5'

C.B.9 RIM ELEV. = 316.1'±
INV. IN FROM C.B.10 = 311.78'
INV. IN FROM C.B.13 = 311.2'
INV. OUT TO C.B.7 = 310.78'

C.B.10 RIM ELEV. = 316.1'±
INV. OUT TO C.B.9 = 312.3'

C.B.11 RIM ELEV. = 319.3'±
INV. OUT TO C.B.12 = 315.6'

C.B.12 RIM ELEV. = 319.3'±
INV. IN FROM C.B.11 = 315.08'
INV. OUT TO C.B.3 = 314.83'

C.B.13 RIM ELEV. = 319.2'±
INV. IN FROM C.B.14 = 313.5'
INV. OUT TO C.B.9 = 313.25'

C.B.14 RIM ELEV. = 321.0'±
INV. IN FROM C.B.15 = 314.75'
INV. OUT FROM C.B.16 = 314.78'
INV. OUT TO C.B.13 = 314.5'

C.B.15 RIM ELEV. = 321.7'±
INV. IN FROM C.B. 17 = 315.2'
INV. OUT TO C.B.14 = 315.0'

C.B.16 RIM ELEV. = 321.0'±
INV. OUT TO C.B.14 = 317.3'

C.B.17 RIM ELEV. = 322.2'±
INV. IN FROM C.B.18 = 317.68'
INV. OUT TO C.B.15 = 317.43'

C.B.18 RIM ELEV. = 322.2'±
INV. IN FROM C.B.19 = 318.4'
INV. OUT TO C.B.17 = 318.2

C.B.19 RIM ELEV. = 322.9'±
INV. IN FROM C.B.20 = 319.65'
INV. OUT TO C.B.18 = 319.4'

C.B.20 RIM ELEV. = 324'±
INV. OUT TO C.B.19 = 321'

CB 21 RIM ELEV= 318.15'±
INV IN FROM CB22 = 314.5'
INV OUT TO CB4 = 314.25'

CB 22 RIM ELEV= 318.15'±
INV OUT TO CB21 = 315'±

NOTE: SEE PLOT MAP ON FILE WITH SURVEY OFFICE.

LEGEND:

- 300' PROPOSED FINISHED CONTOUR
- PROPOSED RETAINING WALL
- PROPOSED LIMIT OF TREES
- PROPOSED MACADAM PAVED DRIVE & BUILDING
- —ST— HDPE STORM SEWER
- C.B.7 CATCH BASIN
- M.H.# SANITARY MANHOLE
- —SS— SANITARY SEWER
- FIRE HYDRANT WITH VALVE
- (1) NUMBER OF DESIGNATED PARKING SPACES
- 314.0' SPOT ELEVATION
- —W— WATER MAIN WITH VALVES

TOWN OF BRUNSWICK PLANNING BOARD	RENSSELAER COUNTY DEPT. OF HEALTH

DANSKIN LAND SURVEYING LLC
P.O. BOX 72
TROY, N.Y. 12181
TEL.: 518-279-8002

REVISIONS:
MAP UPDATED 11-29-06
MAP UPDATED 3-15-07

UTILITY PLAN
SHOWING PROPOSED FINISHED CONTOURS FOR "BRUNSWICK MEADOWS"

TOWN OF BRUNSWICK	RENSSELAER CO., N.Y.
SCALE: 1" = 50'	DATE: 3-13-2006
FIELD: MND	F. BK. #:
OFFICE: RJD	C'KD.: RJD SHEET 3 OF 13